KOLAR DIVISION.

The 7th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 25th December 1897, inclusive, for restoring Betamangala tank and channels, Bowringpet taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 (fifty) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Betamangala tank and channels;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor, will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing approximate quantities of works required to be done for Restoring Betamangala Tank and Channels Serial No. 941 of Ramasagara series.

Item of work.	*Per.*	*Quantity.*
Bund—		
Earthwork to bund watering and tamping	C. yd.	16,200
Raising the new stone work	,,	3,383
Removing and re-fixing old grade stones	No.	42
Turfing	Sq. yds.	12,665
Dismantling and re-building old stone work	C. yds.	1,724
Left bank channel—		
Clearing silt	C. yds.	2,507
Banking	,,	8,593
Blasting rock	,,	50
Repairing the masonry work	Lump sum.	
Constructing aqueduct—		
Excavating earthwork	C. yds.	39
Rough stone in surki mortar	C. ft.	1,043
Burnt stone in surki mortar	,,	1,312
Brick in surki mortar	,,	121
Slabs	S. ft.	338
Concrete	C. ft.	79
Pointing with Portland cement	S. yds.	4·00
Plastering in surki mortar	,,	3·36
Burnt stone work	C. yds.	59
Constructing eight silt dams (each)—		
Earthwork excavation	C. yds.	229
Burnt brick in chunam	C. ft.	203
Burnt stone slabs	C. ft.	169
Chunam plastering	Sqr.	3·36
Rough stone work (new)	C. yds.	89
Constructing nine madaboys (each)—		
Earthwork (foundation)	C. yds.	10
Burnt brick in surki mortar	C. ft.	62
Burnt stone slabs	S. ft.	24
Concrete work	C. ft.	6
Iron pipes including carting, fixing, &c.	R. ft.	14
Chunam plastering	Sqr.	1·14
Bed grade stones	No.	59
Half furlong or bank grade stones	,,	55
Mile stones	,,	4
Gauge stones	,,	3
Right bank channel—		
Earthwork raising bank	C. yds.	660
Brick in surki mortar	C. ft.	40
Burnt stone slabs	C. ft.	27
Constructing silt dams	R. ft.	45
Constructing madaboys	No.	8